



319 S. Grove Avenue – Contributing

Located at 319 S. Grove Avenue is a two-story, frame, gabled ell Folk Victorian dwelling with Italianate influences, built ca. 1890. The dwelling has a continuous brick foundation with a wood water table, an exterior of weatherboard siding, a gable roof of asphalt shingles with wide wood eaves and a cut-off brick flue on the east façade. On the main (W) façade is an original, single-story, hip roof porch set within the ell and enclosed ca. 1920 with single-light casement windows and weatherboard siding. The main entrance has an original, three-horizontal-light and three wood panel door with an aluminum and glass storm door. The interior main entrance has an original, six-light and two wood panel door within a recessed entry. On the south façade is an inset porch with a slightly projecting shed roof, square wood columns and a frame closed railing covered with weatherboard siding on the first floor and an added second floor with a hipped roof and one-over-double hung wood sash windows. The entry on the south façade has a ca. 1970, three-light, diagonal-line wood door with a six-light and two-wood panel exterior door. On the rear façade is an original porch enclosed with single-light fixed windows, a brick foundation and an original single-light glass and wood door. Windows are one-over-one double hung wood sash with wood cornice surrounds. At the basement level are original, three-light and two-light awning windows with wood surrounds. On the rear façade is a wood staircase that leads to a second floor entrance. On the south façade is a concrete cellar entry with double, metal, hinged doors. On both the south and west facades is a two-story, hipped roof bay window each with a dentilled cornice, one-over-one double hung wood sash windows with wood surrounds below which are wood inset panels supported by a brick base. In the gable fields are small circular louvered vents.



To the rear of the dwelling is a ca. 1925, two-bay, frame garage with a front gable roof of corrugated metal seam, an exterior of weatherboard siding, exposed roof rafters, six-over-six double hung wood sash windows and two, original, sixteen-wood panel overhead track doors.

- Contributing